



Project Number: 09052005
Project Name: Cobblestone Winery
Location: Romulos, NY
Date: 05-Sep-05
Prepared By: Radiant Heat Products
Floor Plan: Tasting Room Addition
Circuit Information:

Total Length: 1462 ft PEX 1/2"

Circuit	Length (ft)	Manifold	Tube Type
1	285	Manifold	1/2"
2	294	Manifold	1/2"
3	298	Manifold	1/2"
4	110	Manifold	1/2"
5	233	Manifold 1	1/2"
6	241	Manifold 2	1/2"

Note: Details of the tubing bend radius have been simplified for clarity. Consult tubing manufacturer for specific bend radius recommendations.
 Created using LoopCAD Standard Edition (Version 1.50 (Revision 1))